



## Westbourne Park Packages 3 & 9, 8 and 14

**Client / Consulting Authority:**  
Network Rail

**Date:**  
July 2010 - April 2011

**Project Value:**  
£750k per annum

**Location:**  
West London



### Project Highlights

Cross London Rail Ltd (CRL) is tasked with developing a new railway route called Crossrail. These works, split into a number of Work Packages, will be developed from design through to implementation under a project titled 'Crossrail Critical Advanced Works', of which Colas Rail was awarded Work Package's 3, 8, 9 & 14.

### Project Description

Package 3 & 9: to undertake the relocation of signalling and E&P assets to within the new Network Rail boundary to allow the construction of a new railhead for the Crossrail project at Westbourne Park. The works involved Civils, Signalling, E&P and Telecoms.

Package 8: to enable the installation of new sidings at Westbourne Park for the Crossrail project, Colas Rail installed two No. 6 track portals and two No. TTCs including foundations and also the change over of OHLE wiring and associated works. The installation of the portals was undertaken during a 29hr possession on Christmas Day 2010. The works involved OLE and Civils.

Package 14: to install new 6.6KV a ring main including installation of new troughing routes UTXs, URXs and cable management system. The works involved Civils and E&P.